

MODEL : ASP-150-15

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1 : 180 mVp-p (Max)	I/P : 230VAC O/P : FULL LOAD Ta : 25°C	V1 : 40 mVp-p (Max))	P
2	OUTPUT VOLTAGE TOLERANCE	V1 : 2%~ -2% (Max)	I/P : 110VAC / 264 VAC O/P : FULL/ MIN LOAD Ta : 25°C	V1 : 0.15 %~ -0.15 %	P
3	LINE REGULATION	V1 : 0.5%~ -0.5% (Max)	I/P : 110VAC ~ 264 VAC O/P : FULL LOAD Ta : 25°C	V1 : 0.05 %~ -0.05 %	P
4	LOAD REGULATION	V1 : 1%~ -1% (Max)	I/P : 230 VAC O/P : FULL ~MIN LOAD Ta : 25°C	V1 : 0.12 %~ -0.12 %	P
5	SET UP TIME	230VAC : 3000 ms (Max) 115VAC : 3000 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 1860 ms 115VAC/ 1120 ms	P
6	RISE TIME	230VAC : 80 ms (Max) 115VAC : 80 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 7 ms 115VAC/ 8 ms	P
7	HOLD UP TIME	230VAC : 50 ms (TYP) 115VAC : 16 ms (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 70 ms 115VAC/ 20.5 ms	P
8	OVER/UNDERSHOOT TEST	< ±5%	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	TEST : <5 %	P
9	DYNAMIC LOAD	V1 : 1500 mVp-p	I/P : 230 VAC O/P : FULL /Min LOAD 90%DUTY/1KHZ Ta : 25°C	457 mVp-p	P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	90VAC~264 VAC	I/P : TESTING O/P : FULL LOAD Ta : 25°C	66 V~264V	P
			I/P : LOW-LINE-3V= 107 V HIGH-LINE+15%=300 V O/P : FULL/MIN LOAD ON : 30 Sec . OFF : 30 Sec 10MIN (AC POWER ON/OFF NO DAMAGE)	TEST : OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P : 90VAC ~ 264 VAC O/P : FULL-MIN LOAD Ta : 25°C	TEST : OK	P
3	POWER FACTOR	0.95 / 230 VAC(TYP) 0.98 / 115 VAC(TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	PF= 0.953 / 230 VAC PF= 0.996 / 115 VAC	P
4	EFFICIENCY	88% (TYP)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	89.3 %	P
5	INPUT CURRENT	230V/ 1 A (TYP) 115V/ 2 A (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 0.75 A/ 230 VAC I = 1.43 A/ 115 VAC	P
6	INRUSH CURRENT	230V/ 80 A (TYP) COLD START	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	I = 67 A/ 230 VAC	P
7	LEAKAGE CURRENT	< 2 mA/ 240 VAC	I/P : 254 VAC O/P : Min LOAD Ta : 25°C	L-FG : 0.7 mA N-FG : 0.7 mA	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	105 %-135%	I/P : 230 VAC I/P : 115 VAC O/P : TESTING Ta : 25°C	117 %/ 230 VAC 115 %/ 115 VAC Hiccup Mode	P
2	OVER VOLTAGE PROTECTION	CH1 : 17.5V~ 20.25V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	19.2 V/ 230 VAC 19.2 V/ 115 VAC Shunt down Re- power ON	P
3	OVER TEMPERATURE PROTECTION	SPEC : RTH2 : 90 ± 10°C O.T.P. NO DAMAGE	I/P : 230 VAC O/P : FULL LOAD	O.T.P. Active Shunt down Re-power ON	P
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P : 264 VAC O/P : FULL LOAD Ta : 25°C	NO DAMAGE Hiccup Mode	P

CONTROL FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	NO LOAD POWER CONSUMPTION	<1W	I/P : 240 VAC O/P : NO LOAD	0.6W/240VAC	P

ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	TEMPERATURE RISE TEST	MODEL : ASP-150-12 1. ROOM AMBIENT BURN-IN : 1 HRS I/P : 230VAC O/P : FULL LOAD Ta= 26.7 °C 2. HIGH AMBIENT BURN-IN : 2 HRS I/P : 230VAC O/P : FULL LOAD Ta= 43.2 °C			P
2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR (MIN)	I/P : 230 VAC O/P : 115 % LOAD Ta : 25°C	TEST : OK	P
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 230 VAC O/P : 80% LOAD Ta= -20 °C	TEST : OK	P
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 40°C NO DAMAGE	I/P : 272 VAC O/P : FULL LOAD Ta= 40°C HUMIDITY= 95 %R.H	TEST : OK	P
5	TEMPERATURE COEFFICIENT	± 0.05 %(0-50°C)	I/P : 230 VAC O/P : FULL LOAD	± 0.02 %(0-50°C)	P
6	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10-500Hz (3) Sweep Time : 10min/sweep cycle (4) Acceleration : 2G (5) Test Time : 1 hour in each axis (X.Y.Z) (6) Ta : 25°C		TEST : OK	P

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P : 4.25KVDC/min I/P-FG : 1.5KVAC/min O/P-FG : 0.5KVAC/min	I/P-O/P : 5.1K KVDC/min I/P-FG : 1.8 KVAC/min O/P-FG : 0.6 KVAC/min Ta : 25°C	I/P-O/P : 0.002 mA I/P-FG : 2.52 mA O/P-FG : 0.47 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P : 500VDC>100MΩ I/P-FG : 500VDC>100MΩ O/P-FG : 500VDC>100MΩ	I/P-O/P : 500 VDC I/P-FG : 500 VDC O/P-FG : 500 VDC Ta : 25°C	I/P-O/P : 30 GΩ I/P-FG : 30 GΩ O/P-FG : 30 GΩ NO DAMAGE	P
	APPROVAL	TUV : Certificate NO : UL : File NO : E183223			P

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	PASS	P
2	CONDUCTION	EN55022 CLASS B	I/P : 230 VAC (50HZ) O/P : FULL/50% LOAD Ta : 25°C	PASS Test by certified Lab	P
3	RADIATION	EN55022 CLASS B	I/P : 230 VAC (50HZ) O/P : FULL LOAD Ta : 25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 LIGHT INDUSTRY AIR : 8KV / Contact : 4KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 LIGHT INDUSTRY INPUT : 1KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 LIGHT INDUSTRY L-N : 1KV L,N-PE : 2KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				

M.T.B.F & LIFE CYCLE CALCULATION

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	CAPACITOR LIFE CYCLE	SUPPOSE C105 IS THE MOST CRITICAL COMPONENT I/P : 230VAC O/P : FULL LOAD Ta= 25 °C LIFE TIME= 109811 HRS I/P : 230VAC O/P : FULL LOAD Ta= 40 °C LIFE TIME= 38866 HRS			P
2	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT TOTAL FAILURE RATE : 149.3KHRS			P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	Q1 Rated SPP11N65C3 : 820V 11A	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Full Load (3)Output Short Ta : 25°C	(1) 600 V (2) 600 V (3) 496 V	P
2	Diode Peak Voltage	Q100 Rated STP40NF10L : 100V 40A	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Full Load (3)Output Short Ta : 25°C	(1) 82 V (2) 81 V (3) 70 V	P
3	Clamp Diode Peak Voltage	D2 Rated 1N5406 : 600V 3A	I/P : High-Line +3V = 267 V O/P : (1)Full Load (2) Dynamic Load 90%Duty/1KHz Ta : 25°C	(1) 480 V (2) 476 V	P
4	Input Capacitor Voltage	C5 Rated : 150u / 400V/ 105°C	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change (4)Burn in 1hour Ta : 25°C	(1) 396 V (2) 384 V (3) 396 V (4) 396 V	P
5	Control IC Voltage Test	U2 Rated TEA1552 : 20V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 18.5 V (2) 14.2 V (3) 18.5 V	P
6	Power Transistor (D to S) or (C to E) Peak Voltage	Q2 Rated 2SK3683 : 500V 19A	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Full Load (3)Output Short Ta : 25°C	(1) 406 V (2) 406 V (3) 404 V	P

DATE	SAMPLE	TEST RESULT	TESTER	APPROVAL
2005/12/1	RD SAMPLE	PASS	VINCENT TSENG	MAX LIN
2006/1/25	PRODUCT SAMPLE W0512C45	PASS	VINCENT TSENG	MAX LIN
2006/7/21	PRODUCT SAMPLE W0607A27	PASS	VINCENT TSENG	MAX LIN

2003/12/12 A50-F023