



# Test Report: GSM90B24

---

90W AC-DC Reliable Green Medical Adaptor

## ■ DESIGN VERIFY TEST

- Output Function Test
- Input Function Test
- Protection Function Test
- Control Function Test
- Component Stress Test

## ■ SAFETY & E.M.C. TEST

- Safety Test
- E.M.C. Test

## ■ RELIABILITY TEST

- ENVIRONMENT TEST

■ DESIGN VERIFY TEST

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1 : 180 mVp-p (Max)	I/P : 230VAC O/P : FULL LOAD Ta : 25°C	V1 : 45 mVp-p (Max)	P
2	OUTPUT VOLTAGE TOLERANCE	V1: -3 %~ +3 % (Max)	I/P : 80 VAC / 264 VAC O/P : FULL/ MIN LOAD Ta : 25°C	V1 : -0.74 %~ 0.81 %	P
34	LINE REGULATION	V1 : -1 %~ +1 % (Max)	I/P : 100 VAC ~ 264 VAC O/P : FULL LOAD Ta : 25°C	V1 : 0 %~ 0.13 %	P
4	LOAD REGULATION	V1 : -3 %~ +3 % (Max)	I/P : 230 VAC O/P : FULL ~MIN LOAD Ta : 25°C	V1 : -0.74 %~ 0.81 %	P
5	SET UP TIME	230VAC : 1000 ms (Max) 115VAC : 1500 ms(Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 500 ms 115VAC/ 514 ms	P
6	RISE TIME	230VAC : 50 ms (Max) 115VAC : 50 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 20.1 ms 115VAC/ 20.2 ms	P
7	HOLD UP TIME	230VAC : 30 ms (TYP) 115VAC : 20 ms (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 35.9 ms 115VAC/ 24.1 ms	P
8	OVER/UNDERSHOOT TEST	< ±5%	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	TEST : <5 %	P
9	DYNAMIC LOAD	V1 : 2400 mVp-p	I/P : 230 VAC (1).O/P : FULL /Min LOAD 90%DUTY/ 1KHZ (2).O/P : FULL /Min LOAD 90%DUTY/ 3KHZ (3).O/P : FULL /Min LOAD 90%DUTY/ 5KHZ (4).O/P : FULL /Min LOAD 50%DUTY/ 120HZ Ta : 25°C	(1) 635 mVp-p (2) 512 mVp-p (3) 525 mVp-p (4) 1440 mVp-p	P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
----	-----------	---------------	----------------	--------	---------

1	INPUT VOLTAGE RANGE	80VAC~264 VAC 113VDC~370VDC	(1) I/P:TESTING O/P:FULL LOAD (2) I/P:DC TESTING(L:+ N:-) O/P: FULL / 50% LOAD (3) I/P:DC TESTING(L:- N:+) O/P: FULL / 50% LOAD Ta : 25°C I/P : LOW-LINE-3V= 77 V HIGH-LINE+15%=300 V O/P : FULL/MIN LOAD ON : 30 Sec . OFF : 30 Sec 10MIN ( AC POWER ON/OFF NO DAMAGE )	(1) 67V~264V (2) 106.4Vdc~370Vdc/FULL LOAD 106.3Vdc~370Vdc/50% LOAD (3) 106.4Vdc~370Vdc/FULL LOAD 106.4Vdc~370Vdc/50% LOAD TEST : OK	P
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P : 80 VAC ~ 264 VAC O/P : FULL~MIN LOAD Ta : 25°C	TEST : OK	P
3	POWER FACTOR	0.91/230 VAC(TYP) 0.95/ 115 VAC(TYP)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	PF= 0.957 230VAC PF= 0.988 115VAC	P
4	EFFICIENCY	90 % (TYP)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	90.5 %	P
5	INPUT CURRENT	230V/ 0.6 A (TYP) 115V/ 1.3 A (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 0.439 A/ 230 VAC I = 0.865 A/ 115 VAC	P
6	INRUSH CURRENT	230V/ 60 A (TYP) 115V/ 30 A (TYP) COLD START	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 44.5 A/ 230 VAC I = 21.9 A/ 115 VAC	P
7	LEAKAGE CURRENT	< 100 uA / 264VAC For Touch	I/P : 264 VAC O/P : Min LOAD Ta : 25°C	L/N-V+: 67.6 μA L/N-V-: 66.5 μA	P
8	NO LOAD CONSUMPTION	< 0.15 W	I/P : 240VAC O/P : NO LOAD Ta : 25°C	< 0.0726 W	P
9	ERP STEP2 COMPLIANT	LEVEL VI	I/P: 230 VAC/115VAC O/P:100/75/50/25% Ta:25°C	230V 90.460 % 115V 89.372 %	P

**PROTECTION FUNCTION TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	110 % ~150 %	I/P : 230 VAC I/P : 115 VAC O/P : TESTING Ta : 25°C	133.6 %/ 230 VAC 128.3 %/ 115 VAC Protection type : Hiccup mode, recovers automatically after fault condition is removed	P
2	OVER VOLTAGE PROTECTION	CH1 : 25.2 V ~ 32.4 V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	29.59 V/ 230 VAC 29.56 V/ 115 VAC Protection type : Shut down o/p voltage, re-power on to recover	P
3	OVER TEMPERATURE PROTECTION	Shut down o/p voltage, re-power on to recover	I/P : 230 VAC O/P : FULL LOAD	O.T.P. Active Shut down o/p voltage, re-power on to recover	P

4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P : 264 VAC O/P : FULL LOAD Ta : 25°C	NO DAMAGE Hiccup Mode	P
---	------------------	--	---	--------------------------	---

**COMPONENT STRESS TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor ( D to S) or (C to E) Peak Voltage	Q32 Rated : 650 V 10.6 A	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 612 V (2) 496 V (3) 586 V	P
2	Diode Peak Voltage	Q101 Rated : 150 V 43 A	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2)Output Short (3)Full load continue Ta : 25°C	(1) 138 V (2) 135 V (3) 137 V	P
3	Input Capacitor Voltage	C 5 Rated : 100u /400V/105°C	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 392 V (2) 384 V (3) 396 V	P
4	Control IC Voltage Test	U 1 Rated : 28 V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 17.8 V (2) 17.4 V (3) 18.1 V	P
5	CLAMP DIODE	D 3 Rated : 800 V 2 A	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 525 V (2) 426 V (3) 526 V	P
6	Power Transistor ( D to S) or (C to E) Peak Voltage	Q31 Rated : 500V 19 A	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 428 V (2) 388 V (3) 405 V	P

**SAFETY & E.M.C. TEST**

**SAFETY TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P : 4 KVAC/min	I/P-O/P : 4.2KVAC/min Ta : 25°C	I/P-O/P : 1.865 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P : 500VDC>100MΩ	I/P-O/P : 500 VDC	I/P-O/P : 9999 MΩ	P

			Ta : 25°C/70% RH	NO DAMAGE	
--	--	--	------------------	-----------	--

**E.M.C TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	BS EN/EN61000-3-2 CLASS A	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	PASS	P
2	CONDUCTION	BS EN/EN55011 (CISPR11), FCC PART 15 /CISPR22, CAN ICES-3(B)/NMB-3(B) CLASS B	I/P : 230 VAC (50HZ) O/P : FULL/50% LOAD Ta : 25°C	PASS Test by certified Lab	P
3	RADIATION	BS EN/EN55011 (CISPR11), FCC PART 15 /CISPR22, CAN ICES-3(B)/NMB-3(B) CLASS B	I/P : 230 VAC (50HZ) O/P : FULL LOAD Ta : 25°C	PASS Test by certified Lab	P
4	E.S.D	BS EN/EN61000-4-2 AIR : 15KV / Contact : 8KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
5	E.F.T	BS EN/EN61000-4-4 INPUT: 2KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
6	SURGE	BS EN/EN61000-4-5 L-N : 1KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				

■ **RELIABILITY TEST**

**ENVIRONMENT TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	TEMPERATURE RISE TEST	MODEL : GSM90B24 1. ROOM AMBIENT BURN-IN : 2 HRS I/P : 230VAC O/P : FULL LOAD Ta= 21.6°C 2. HIGH AMBIENT BURN-IN : 2 HRS I/P : 230VAC O/P : FULL LOAD Ta= 40.2°C			P

			NO	Position	ROOM AMBIENT Ta= 21.6 °C	HIGH AMBIENT Ta= 40.2°C																																																																					
			1	LF1	60.7°C	81.1°C			2	LF2	57.4°C	78.6°C	3	L2	65.5°C	87.3°C	4	BD1	59.4°C	79.9°C	5	LF3	64.1°C	86.4°C	6	C11	62.0°C	83.9°C	7	Q31	66.5°C	88.5°C	8	Q32	66.3°C	87.5°C	9	D1	73.8°C	96.6°C	10	D30	77.4°C	99.2°C	11	C5	66.3°C	88.5°C	12	C52	70.0°C	92.3°C	13	RTH30	67.5°C	89.4°C	14	Q101	72.0°C	93.1°C	15	C101	58.6°C	79.2°C	16	LF101	56.3°C	76.4°C	17	U2	65.9°C	87.3°C	18	D33	70.8°C
2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR ( MIN )			I/P : 230 VAC O/P : 127% LOAD Ta : 25°C	TEST : OK			P																																																																		
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR			I/P : 264VAC/100VAC O/P : 100 % LOAD Ta= -35 °C	TEST : OK			P																																																																		
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 40 °C NO DAMAGE			I/P : 272 VAC O/P : FULL LOAD Ta= 40°C HUMIDITY= 95 %R.H	TEST : OK			P																																																																		
5	TEMPERATURE COEFFICIENT	± 0.03%/°C (0-50°C)			I/P : 230 VAC O/P : FULL LOAD	± 0.01%/°C (0-50°C)			P																																																																		
6	STORAGE TEMPERATURE TEST	1. Thermal shock Temperature : -40°C~ +85°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 5 CYCLE 5. Input/Output condition : STATIC			OK			P																																																																			
7	THERMAL SHOCK TEST	1. Thermal shock Temperature : -30°C~ +60°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 230VAC/Full Load AC ON/OFF TEST turn on 58sec ; turn off 2sec			OK			P																																																																			
8	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10~500Hz (3) Sweep Time : 12min/sweep cycle (4) Acceleration : 2G (5) Test Time : 60min in each axis (X.Y.Z) (6) Ta : 25°C			TEST : OK			P																																																																			



9	CAPACITOR LIFE CYCLE	SUPPOSE C 101 IS THE MOST CRITICAL COMPONENT (1) I/P : 230VAC O/P : FULL LOAD Ta= 25°C LIFE TIME (2) I/P : 230VAC O/P : FULL LOAD Ta= 40°C LIFE TIME (3) I/P : 230VAC O/P : 75% LOAD Ta= 40°C LIFE TIME (4) I/P : 230VAC O/P : 50% LOAD Ta= 40°C LIFE TIME	(1) 156516HRS (2) 48146HRS (3) 91764HRS (4) 126246HRS	P
10	MTBF	2743.3K hrs min. Telcordia SR-332 (Bellcore) ; 353.3K hrs min. MIL-HDBK-217F (25°C)		P
11	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure (Expected Life): Above 30,000 hours @ TA 40°C		P

SAMPLE	TEST RESULT	TESTER	APPROVAL
PRODUCT SAMPLE	PASS	Shenym	Wangdz

2007/3/20 A50-S014