



Test Report: GST40A18

40W AC-DC Reliable Green Industrial Adaptor

■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Component Stress Test

■ SAFETY & E.M.C. TEST

Safety Test

E.M.C. Test

■ RELIABILITY TEST

ENVIRONMENT TEST

■ DESIGN VERIFY TEST

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE(Max)	V1: 120mVp-p	I/P:230VAC O/P:FULL LOAD Ta:25°C	V1: 35.8mVp-p	P
2	OUTPUT VOLTAGE(Max) TOLERANCE	V1: -3%~ 3%	I/P: 100VAC /264VAC O/P:FULL/ MIN. LOAD Ta:25°C	V1: -0.24 %- 0.28 %	P
3	LINE REGULATION (Max)	V1: -1%~ 1%	I/P: 100VAC~ 264VAC O/P:FULL LOAD Ta:25°C	V1: 0 %- 0.034 %	P
4	LOAD REGULATION(Max)	V1: -3%~ 3%	I/P: 230VAC O/P:FULL -MIN LOAD Ta:25°C	V1: -0.24 %- 0.28 %	P
5	SET UP TIME(Max)	230VAC/1000ms 115VAC/1000ms	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 558.431 ms 115VAC/ 631.111 ms	P
6	RISE TIME (Max)	230VAC/50ms 115VAC/50ms	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 43.023 ms 115VAC/ 36.048 ms	P
7	HOLD UP TIME(Typ)	230VAC/50ms 115VAC/15ms	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 148.887 ms 115VAC/ 40.653 ms	P
8	OVER/UNDERSHOOT TEST	< ±5%	I/P: 230VAC O/P:FULL LOAD Ta:25°C	< ±5%	P
9	DYNAMIC LOAD	V1: 1800mVp-p	I/P: 230VAC O/P(1)FULL /Min LOAD 90%DUTY / 1KHZ (2) (1)FULL /Min LOAD 90%DUTY / 3KHZ (3)FULL /Min LOAD 90%DUTY / 5KHZ (4)FULL /Min LOAD 50%DUTY / 120HZ Ta:25°C	202mVp-p 190mVp-p 203mVp-p 632mVp-p	P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	90VAC~264VAC	I/P:TESTING O/P:FULL LOAD Ta:25°C	64. 243 V~264V	P
			I/P: (1)LOW-LINE-3V=87 V HIGH-LINE+15%=300 V O/P:FULL/MIN LOAD ON: 30 Sec OFF: 30 Sec 10MIN (2)230Vac ON: 0.5 Sec OFF: 0.5 Sec 20MIN (3)230Vac ON:3Sec OFF:3Sec 12HOURS (POWER ON/OFF NO DAMAGE)	TEST:OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE	I/P:100 VAC ~264 VAC O/P:FULL-MIN LOAD Ta:25°C	TEST: OK	P
4	EFFICIENCY(TYP)	90%	I/P:230 VAC O/P:FULL LOAD Ta:25°C	90.60%	P
5	INPUT CURRENT (Typ)	230V/ 0.5 A 115V/ 1 A	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 0.327A/ 230VAC I = 0.630A/ 115VAC	P
6	INRUSH CURRENT(Typ)	230V/65A 115V/35A COLD START	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I =42. 726A/ 230VAC I =22. 368A/ 115VAC	P
7	LEAKAGE CURRENT	< 0.75 mA / 240 VAC	I/P : 240 VAC O/P : Min LOAD Ta : 25°C	L-FG : 0. 376 mA N-FG : 0. 376 mA	P
8	NO LOAD CONSUMPTION	< 0.075 W	I/P : 115VAC I/P : 230VAC O/P : NO LOAD Ta : 25°C	< 0.0426 W < 0.0426 W	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	105%~ 150%	I/P: 230VAC I/P: 115VAC O/P: TESTING Ta:25°C	133.78%/ 230VAC 131.98%/115VAC Hiccup Mode	P
2	OVER VOLTAGE PROTECTION	CH:18.9V~24.3V	I/P: 230VAC I/P: 115VAC O/P: MIN LOAD Ta:25°C	24.0V/ 230VAC 24.0V/115VAC Shut down Re- power ON	P
3	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P: 264VAC O/P: FULL LOAD Ta:25°C	NO DAMAGE Hiccup Mode	P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	PWM Transistor (D to S) or (C to E) Peak Voltage	Q1 Rated : 6A/ 800 V	I/P: High-Line +3V =267V AC ON/OFF VDS: O/P: (1) Full Load (2) Output Short (3) Full Load Continue Ta:25°C	VDS (1) 544V (2) 404V (3) 534V	P
2	Diode Peak Voltage	Q100 Rated : 20A/ 100 V	I/P: High-Line +3V =267 V AC ON/OFF O/P: (1) Full Load (2) Output Short (3) Dynamic Load 100% Load/ Min. Load 50%Duty/120Hz (4) 0%→400% Load. Ta:25°C	Q100: (1) 64.0 V (2) 47.2V (3) 64.6V (4) 65.2V	P
3	Input Capacitor Voltage	C5 Rated: : 120 μ / 400V 105°C	I/P: High-Line +3V =267 V O/P: (1) Full Load input on/off (2) Min load input on /Off (3) Full Load /Min load Change Ta:25°C	(1) 356V (2) 356V (3) 358V	P
4	Control IC Voltage Test	PWM IC U1 Rated : 30V -0.4V(MIN.)	I/P: High-Line +3V =267 V AC ON/OFF O/P(1) FULL LOAD (2) Output Short (3) O.L.P (4) O.V.P. (5) NO LOAD VR MIN LOW LINE Ta:25°C	(1) 26.1V (2) 26.0V (3) 25.9V (4) 15.1V (5) 20.2V	P



5	Clamp Diode Peak Voltage	D1 Rated : 1000V 1A	I/P : High-Line +3V = 267 V AC ON/OFF O/P : (1) Dynamic Load 90%Duty/1KHz (2) Full load continue Ta : 25°C	(1) 508 V (2) 502 V	P
---	--------------------------	---------------------	---	------------------------	---

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P: 3KVAC/min I/P-FG: 2KVAC/min O/P-FG: 0.5KVAC/min	I/P-O/P: 3.6 KVAC/min I/P-FG: 2.4 KVAC/min O/P-FG: 0.6 KVAC/min Ta: 25°C	I/P-O/P: 1.375mA I/P-FG: 5.512mA O/P-FG: 0.464mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P: 500VDC > 100MΩ I/P-FG: 500VDC > 100MΩ O/P-FG: 500VDC > 100MΩ	I/P-O/P: 500 VDC I/P-FG: 500 VDC O/P-FG: 500 VDC Ta: 25°C	I/P-O/P: 9999MΩ I/P-FG: 9999 MΩ O/P-FG: 9999MΩ NO DAMAGE	P

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A	I/P: 230VAC/50HZ O/P: 100%, 75%, 50% OAD Ta: 25°C	PASS	P
2	CONDUCTION	EN55022 CLASS B	I/P : 230 VAC (50HZ) O/P : FULL/50% LOAD Ta : 25°C	PASS Test by certified Lab	P
3	RADIATION	EN55022 CLASS B	I/P : 230 VAC (50HZ) O/P : FULL LOAD Ta : 25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 AIR : 15KV / Contact : 8KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 INPUT : 1KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
6	SURGE	EN61000-4-5 L-N : 1KV L,N-PE : 2KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				

■ RELIABILITY TEST

ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT																																																				
1	TEMPERATURE RISE TEST	MODEL : GST40A24 1. ROOM AMBIENT BURN-IN : 1 HRS I/P : 230VAC O/P : FULL LOAD Ta= 17.5 °C 2. HIGH AMBIENT BURN-IN : 1 HRS I/P : 230VAC O/P : FULL LOAD Ta= 47.5 °C	<table border="1"> <thead> <tr> <th>NO</th> <th>Position</th> <th>ROOM AMBIENT Ta= 17.5 °C</th> <th>HIGH AMBIENT Ta= 47.5 °C</th> </tr> </thead> <tbody> <tr><td>1</td><td>LF1</td><td>39.3°C</td><td>70.9°C</td></tr> <tr><td>2</td><td>LF2</td><td>42.3°C</td><td>73.5°C</td></tr> <tr><td>3</td><td>BD1</td><td>47.7°C</td><td>77.5°C</td></tr> <tr><td>4</td><td>C5</td><td>42.3°C</td><td>73.7°C</td></tr> <tr><td>5</td><td>C15</td><td>45.3°C</td><td>77.3°C</td></tr> <tr><td>6</td><td>R22</td><td>42.6°C</td><td>74.0°C</td></tr> <tr><td>7</td><td>T1</td><td>49.1°C</td><td>80.3°C</td></tr> <tr><td>8</td><td>Q1</td><td>42.2°C</td><td>74.7°C</td></tr> <tr><td>9</td><td>C104</td><td>38.9°C</td><td>70.8°C</td></tr> <tr><td>10</td><td>U1</td><td>41.6°C</td><td>72.9°C</td></tr> <tr><td>11</td><td>D1</td><td>57.3°C</td><td>90.9°C</td></tr> <tr><td>12</td><td>R6</td><td>61.0°C</td><td>92.4°C</td></tr> </tbody> </table>	NO	Position	ROOM AMBIENT Ta= 17.5 °C	HIGH AMBIENT Ta= 47.5 °C	1	LF1	39.3°C	70.9°C	2	LF2	42.3°C	73.5°C	3	BD1	47.7°C	77.5°C	4	C5	42.3°C	73.7°C	5	C15	45.3°C	77.3°C	6	R22	42.6°C	74.0°C	7	T1	49.1°C	80.3°C	8	Q1	42.2°C	74.7°C	9	C104	38.9°C	70.8°C	10	U1	41.6°C	72.9°C	11	D1	57.3°C	90.9°C	12	R6	61.0°C	92.4°C		P
NO	Position	ROOM AMBIENT Ta= 17.5 °C	HIGH AMBIENT Ta= 47.5 °C																																																						
1	LF1	39.3°C	70.9°C																																																						
2	LF2	42.3°C	73.5°C																																																						
3	BD1	47.7°C	77.5°C																																																						
4	C5	42.3°C	73.7°C																																																						
5	C15	45.3°C	77.3°C																																																						
6	R22	42.6°C	74.0°C																																																						
7	T1	49.1°C	80.3°C																																																						
8	Q1	42.2°C	74.7°C																																																						
9	C104	38.9°C	70.8°C																																																						
10	U1	41.6°C	72.9°C																																																						
11	D1	57.3°C	90.9°C																																																						
12	R6	61.0°C	92.4°C																																																						
2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR (MIN)	I/P : 230 VAC O/P : 120 % LOAD Ta : 25°C	TEST : OK	P																																																				
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 264VAC/100VAC O/P : 100 % LOAD Ta= -30 °C	TEST : OK	P																																																				
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 50 °C NO DAMAGE	I/P : 272 VAC O/P : FULL LOAD Ta= 50.1 °C HUMIDITY= 95 %R.H	TEST : OK	P																																																				
5	TEMPERATURE COEFFICIENT	± 0.03 %/°C (0-50°C)	I/P : 230 VAC O/P : FULL LOAD	± 0.004 %/°C (0-50°C)	P																																																				
6	STORAGE TEMPERATURE TEST	1. Thermal shock Temperature : -40°C~ +85°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 5 CYCLE 5. Input/Output condition : STATIC		OK	P																																																				
7	THERMAL SHOCK TEST	1. Thermal shock Temperature : -30°C~ +70°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 230VAC/Full Load AC ON/OFF TEST turn on 58sec ; turn off 2sec		OK	P																																																				



8	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10-500Hz (3) Sweep Time : 10min/sweep cycle (4) Acceleration : 2G (5) Test Time : 60min in each axis (X.Y.Z) (6) Ta : 25°C	TEST : OK	P
9	CAPACITOR LIFE CYCLE	SUPPOSE C104 IS THE MOST CRITICAL COMPONENT (1) I/P : 230VAC O/P : FULL LOAD Ta= 25 °C LIFE TIME (2) I/P : 230VAC O/P : FULL LOAD Ta= 50 °C LIFE TIME (3) I/P : 230VAC O/P : 75% LOAD Ta= 50 °C LIFE TIME (4) I/P : 230VAC O/P : 50% LOAD Ta= 50 °C LIFE TIME	(1) 500068HRS (2) 89027HRS (3) 128547HRS (4) 131216HRS	P
10	MTBF	MIL-HDBK-217F TOTAL FAILURE RATE : 736.4 KHRS		P
11	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure (Expected Life): Above 30,000 hours @ TA 50°C		P

TEST RESULT	TESTER	REVIEW	APPROVAL
PASS	FRANK	GESG	WANGDZ

2007/3/20 A50-S014