



Test Report: HLG-240-24

240W Single Output Switching Power Supply

■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Other Test

Component Stress Test

■ SAFETY & E.M.C. TEST

Safety Test

E.M.C. Test

■ RELIABILITY TEST

DESIGN VERIFY TEST

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1: 150 mVp-p (Max)	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	V1: 34.4 mVp-p (Max)	P
2	OUTPUT VOLTAGE ADJUST RANGE	CH1: 22.4 V~25.6 V	I/P: 230 VAC I/P:115VAC O/P:MIN LOAD Ta:25°C	21.96V~ 26.34 V /230VAC 21.96V~26.34 V/115VAC	P
3	CURRENT ADJ RANGE	5A~10A	I/P: 230 VAC O/P: CV=Vo-2V Ta:25°C	0.2A~ 10.96 A	P
4	CONSTANT CURRENT REGION	12V~24V	I/P: 230 VAC O/P:CV MODE Ta:25°C	O/P=12V: 10.532 A O/P=23V: 10.331 A	P
5	OUTPUT VOLTAGE TOLERANCE	V1: -1% ~ 1% (Max)	I/P: 100 VAC /264VAC O/P:FULL/ 0% LOAD Ta:25°C	V1: -0.29% ~ 0.29%	P
6	LINE REGULATION	V1: -0.5% ~ 0.5% (Max)	I/P:100 VAC ~264 VAC O/P:FULL LOAD Ta:25°C	V1: 0% ~ 0%	P
7	LOAD REGULATION	V1: -0.5% ~ 0.5% (Max)	I/P: 230 VAC O/P:FULL ~MIN LOAD Ta:25°C	V1: -0.29% ~ 0.29%	P
8	SET UP TIME	230VAC/ 2500 ms (Max) 115VAC/ 2500 ms (Max)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 1729 ms 115 VAC/ 1878 ms	P
9	RISE TIME	230VAC/ 80 ms (Max) 115VAC/ 80 ms (Max)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 43 ms 115 VAC/ 43 ms	P
10	HOLD UP TIME	230VAC/ 15 ms (Typ) 115VAC/ 15 ms (Typ)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 22 ms 115 VAC/ 22 ms	P
11	OVER/UNDERSHOOT TEST	< ±5%	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	TEST:< 5%	P
12	DYNAMIC LOAD	V1: 2400 mVp-p	I/P: 230 VAC O/P:(1)FULL 90%DUTY/1KHZ Ta:25°C	256mVp-p	P

13	DIMMER TEST (B Type only)	SPEC:											
		*Reference resistance value for output current adjustment (Typical)											
		Resistance value	10K	20K	30K	40K	50K	60K	70K	80K	90K	100K	
		Output current	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%	
		*1 ~ 10V dimming function for output current adjustment (Typical)											
		Dimming value	1V	2V	3V	4V	5V	6V	7V	8V	9V	10V	
		Output current	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%	
		*10V PWM signal for output current adjustment (Typical)											
		Duty value	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%	
		Output current	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%	
		TEST RESULT: I/P : 230 VAC ; Ta : 25°C											
		1	Resistance value	10K	20K	30K	40K	50K	60K	70K	80K	90K	100K
			Output current	1.624A	3.191A	4.681A	6.476A	7.695A	9.177A	10.614A	12.122A	13.437A	14.255A
%	10.83%		21.27%	31.21%	43.17%	51.30%	61.18%	70.76%	80.81%	89.58%	95.03%		
2	Dimming value		1V	2V	3V	4V	5V	6V	7V	8V	9V	10V	
	Output current		1.649A	3.304A	4.696A	6.215A	7.704A	9.197A	10.702A	12.242A	13.733A	15.035A	
	%		10.99%	22.03%	31.31%	41.43%	51.36%	61.31%	71.35%	81.61%	91.55%	100.23%	
3	Duty value		10%	20%	30%	40%	50%	60%	70%	80%	90%	100%	
	Output current		1.796A	3.415A	4.879A	6.358A	7.825A	9.281A	10.729A	12.179A	13.636A	15.098A	
	%		11.97%	22.77%	32.53%	42.39%	52.17%	61.87%	71.53%	81.19%	90.91%	100.65%	

P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	90VAC~264 VAC	I/P:TESTING O/P:FULL LOAD Ta:25°C	64V~264V	P
			I/P: (1)LOW-LINE-3V=87 V (2)HIGH-LINE=264 V O/P:FULL/MIN LOAD ON: 30 Sec . OFF: 30 Sec 10MIN (AC POWER ON/OFF NO DAMAGE)	TEST: OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P: 100 VAC ~264VAC O/P:FULL~MIN LOAD Ta:25°C	OK	P
3	POWER FACTOR	0.95/ 230 VAC FULL LOAD (TYP) 0.98/ 115 VAC FULL LOAD (TYP) 0.9/ 230 VAC 65% LOAD (TYP) 0.9/ 115 VAC 65%LOAD (TYP)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD / 65% LOAD Ta:25°C	PF=0.95 /230V/100%LOAD PF=0.99 /115V/100%LOAD PF=0.91 /230V/65%LOAD PF=0.99 /115V/65%LOAD	P
4	EFFICIENCY	93% (TYP)	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	93.98 %	P
5	INPUT CURRENT	230 V/ 2 A (Typ) 115 V/ 4 A (Typ)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	I = 1.16 / 230VAC I = 2.3 / 115VAC	P
6	INRUSH CURRENT	230 V/ 75A (Typ) COLD START	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	I = 57 A/ 230VAC	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	95 %~108 %	I/P: 264 VAC I/P: 230 VAC I/P: 100 VAC O/P:TESTING Ta:25°C	103.7 %/264VAC 103.7 %/ 230VAC 103.7 %/100VAC Constant Current Limiting	P
2	OVER VOLTAGE PROTECTION	V1: 26V~ 33V	I/P: 264 VAC I/P: 230 VAC I/P: 90 VAC O/P:MIN LOAD Ta:25°C	28.05 V/264VAC 27.96 V/ 230VAC 28.2 V/ 90VAC Shunt down Re- power ON	P
3	OVER TEMPERATURE PROTECTION	SPEC: TSW1: 105±5°C O.T.P. NO DAMAGE	I/P: 230 VAC O/P:FULL LOAD	O.T.P. Active Shut down o/p volotage , recovers automatically after temperature goes down	P
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P: 264VAC O/P: FULL LOAD Ta:25°C	NO DAMAGE Hiccup Mode	P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	Q3 Rated IRFB20N50K 20A/ 500V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 438 V (2) 420 V (3) 442 V	P
2	Diode Peak Voltage	Q101 Rated IRFB3607PBF 80A/75V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2)Output Short (3)Full load continue Ta : 25°C	(1) 53 V (2) 12 V (3) 53 V	P
		Q102 Rated IRFB3607PBF 80A/75V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2)Output Short (3)Full load continue Ta : 25°C	(1) 56 V (2) 21 V (3) 55 V	
3	Input Capacitor Voltage	C5 Rated: NCC: 150μ/420 V/105°C	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 397 V (2) 414 V (3) 415 V	P
4	Control IC Voltage Test	U 70 Rated L6599AD : 8.85V~16 V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 12.9 V (2) 12.9 V (3) 12.9 V	P
5	P.F.C Transistor (D to S) or (C to E) Peak Voltage	Q1 Rated STW25NM50N 22A/500V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2)Output Short (3)Full load continue Ta : 25°C	(1) 484 V (2) 472 V (3) 474 V	P

SAFETY & EMC TEST

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	IEC60950-1 I/P-O/P: 3.75KVAC/min<10mA I/P-FG:2KVAC/min<10mA O/P-FG:0.5KVAC/min<10mA	I/P-O/P: 4 KVAC/min I/P-FG: 2.4KVAC/min O/P-FG: 0.6 KVAC/min Ta:25°C	I/P-O/P: 4.85 mA I/P-FG: 4.29 mA O/P-FG: 5.08 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P:500VDC>100MΩ I/P-FG: 500VDC>100MΩ O/P-FG:500VDC>100MΩ	I/P-O/P: 500 VDC I/P-FG: 500 VDC O/P-FG: 500 VDC Ta:25°C	I/P-O/P: 20.9 GΩ I/P-FG: 15.5 GΩ O/P-FG: 30 GΩ NO DAMAGE	P
3	GROUNDING CONTINUITY	IEC60950-1 FG(PE) TO CHASSIS OR TRACE < 100 mΩ	40A / 2min Ta:25°C	13 mΩ	P
4	LEAKAGE CURRENT	IEC60950-1 < 0.75 mA / 240VAC	I/P: 264 VAC O/P:Min LOAD Ta:25°C	L-FG: 0.35 mA N-FG: 0.34 mA	P
5	APPROVAL	TUV: Certificate NO : R50171244 UL: File NO :			P

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A CLASS C	I/P: 240VAC/50HZ LOAD:LED/ELECTRONIC LOAD O/P:100%/50% LOAD Ta:25°C	PASS	P
2	CONDUCTION	EN55022 EN55015 CLASS B	I/P: 230 VAC (50HZ) O/P:FULL/50% LOAD Ta:25°C	PASS Test by certified Lab	P
3	RADIATION	EN55022 EN55015 CLASS B	I/P: 230 VAC (50HZ) O/P:FULL LOAD Ta:25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 LIGHT INDUSTRY AIR:8KV / Contact:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 LIGHT INDUSTRY INPUT: 2KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 LIGHT INDUSTRY L-N :2KV L,N-PE:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P



8	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10~500Hz (3) Sweep Time : 12min/sweep cycle (4) Acceleration : 5G (5) Test Time : 72min in each axis (X.Y.Z) (6) Ta : 25°C	TEST : OK	P
9	CAPACITOR LIFE CYCLE	HLG-240H-24:SUPPOSE C102 IS THE MOST CRITICAL COMPONENT (1) I/P : 230VAC O/P : FULL LOAD Ta= 25 °C LIFE TIME (2) I/P : 230VAC O/P : FULL LOAD Ta= 60 °C LIFE TIME (3) I/P : 230VAC O/P : 75% LOAD Ta= 60 °C LIFE TIME	(1) 196640 HRS (2) 27898.3 HRS (3) 54198.9 HRS	P
10	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT Mean Time Between Failure : 207.9K HRS		P
11	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure(Expected Life) : 50,000 hours @ Tcase 70°C		P

DATE	SAMPLE	TEST RESULT	TESTER	APPROVAL
2009/7/31	RD SAMPLE	PASS	SANFORD SU	VINCENT TSENG
2009/9/29	PRODUCT SAMPLE W0907E29	PASS	SANFORD SU	VINCENT TSENG
2009/12/2	PRODUCT SAMPLE W0910C36	PASS	SANFORD SU	VINCENT TSENG

2003/12/12 A50-F023