

MODEL:PSP-600-13.5

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1: 240 mVp-p (Max)	I/P: 230VAC O/P:FULL LOAD Ta:25°C	V1: 108 mVp-p (Max)	P
2	OUTPUT VOLTAGE ADJUST RANGE	CH1: 12V- 15 V	I/P: 230 VAC I/P: 115 VAC O/P:MIN LOAD Ta:25°C	11.47 V- 16.25 V/ 230 VAC 11.47 V- 16.25 V/ 115 VAC	P
3	OUTPUT VOLTAGE TOLERANCE	V1: 1 %- -1 % (Max)	I/P: 155 VAC / 264 VAC O/P:FULL/ MIN LOAD Ta:25°C	V1: 0.3 %- -0.3 %	P
4	LINE REGULATION	V1: 0.5 %- -0.5 % (Max)	I/P: 155VAC ~ 264 VAC O/P:FULL LOAD Ta:25°C	V1: 0.05 %- -0.05 %	P
5	LOAD REGULATION	V1: 0.5 %- -0.5 % (Max)	I/P: 230 VAC O/P:FULL ~MIN LOAD Ta:25°C	V1: 0.23 %- -0.23 %	P
6	SET UP TIME	230VAC: 1500 ms (Max) 115 VAC: 1500 ms (Max)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 1191 ms 115VAC/ 1191 ms	P
7	RISE TIME	230VAC: 50 ms (Max) 115VAC: 50 ms (Max)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 2 ms 115VAC/ 2 ms	P
8	HOLD UP TIME	230VAC: 16 ms (TYP) 115VAC: 16 ms (TYP)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 21 ms 115VAC/ 21 ms	P
9	OVER/UNDERSHOOT TEST	< ±5%	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	TEST: <5 %	P
10	DYNAMIC LOAD	V1: 1350 mVp-p	I/P: 230 VAC O/P:FULL /Min LOAD 90%DUTY/1KHZ Ta:25°C	1016 mVp-p	P

INPUT FUNCTION TEST

N O	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	88VAC~264 VAC	I/P:TESTING O/P:FULL LOAD Ta:25°C	69V~264V	P
			I/P: LOW-LINE-3V= 85 V HIGH-LINE+15%=300 V O/P:FULL/MIN LOAD ON: 30 Sec . OFF: 30 Sec 10MIN (AC POWER ON/OFF NO DAMAGE)	TEST: OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P: 88 VAC ~ 264 VAC O/P:FULL-MIN LOAD Ta:25°C	TEST: OK	P
3	POWER FACTOR	0.95 / 230 VAC(TYP) 0.98 / 115 VAC(TYP)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	PF= 0.96 / 230 VAC PF= 0.99 / 115 VAC	P
4	EFFICIENCY	85% (TYP)	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	86.1 %	P
5	INPUT CURRENT	230V/ 4.1 A(TYP) 115V/ 8.2 A(TYP)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	I = 3.2 A/ 230 VAC I = 6.6 A/ 115 VAC	P
6	INRUSH CURRENT	230V/ 50 A(TYP) 115V/ 25 A(TYP) COLD START	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	I = 29 A/ 230 VAC I = 15 A/ 115 VAC	P
7	LEAKAGE CURRENT	< 1.5 mA / 240 VAC	I/P: 254 VAC O/P:Min LOAD Ta:25°C	L-FG: 0.98 mA N-FG: 0.98 mA	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	105%~ 135 %	I/P: 230 VAC I/P: 115 VAC O/P: TESTING Ta:25°C	123 %/ 230 VAC 123 %/ 115 VAC Constant current limiting	P
2	OVER VOLTAGE PROTECTION	CH1: 15.5 V~ 18.2 V	I/P: 230 VAC I/P: 115 VAC O/P: MIN LOAD Ta:25°C	17.1 V/ 230 VAC 17.1 V/ 115 VAC Shunt down Re- power ON	P
3	OVER TEMPERATURE PROTECTION	SPEC: TSW1: 85± 5°C O.T.P TSW2: 80± 5°C O.T.P NO DAMAGE	I/P: 230 VAC O/P: FULL LOAD	O.T.P. Active Shut down o/p voltage , recovers automatically after temperature goes down , than re-power on to recover	P
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P: 264 VAC O/P: FULL LOAD Ta:25°C	NO DAMAGE Foldback Current Limiting	P

CONTROL FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	FAN SPEED CONTROL	-----	I/P: 230 VAC O/P: FULL LOAD Ta:25°C	Fan Voltage= 10.78 V	P
2	REMOTE CONTROL	Rc+ / Rc- SHORT POWER ON OPEN POWER OFF	I/P: 230 VAC O/P: FULL LOAD Ta:25°C	SHORT POWER ON OPEN POWER OFF	P
3	POWER OK	POWER ON : 3.3V~6V POWER OFF : 0V~2V	I/P: 230 VAC I/P: 115 VAC O/P: FULL LOAD Ta:25°C	POWER ON : 4.88 V POWER OFF : 0 V	P
4	CURRENT SHARING	PSU1-PSU2 < 10%	I/P: 230 VAC O/P: FULL/50% LOAD Ta:25°C	O/P: 100% PSU1: 720 W PSU2: 707 W O/P: 50% PSU1: 362 W PSU2: 343 W	P
5	REMOTE SENSE	>0.3V	I/P: 230 VAC O/P: FULL LOAD Ta:25°C	>0.3V	P

ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	TEMPERATURE RISE TEST	MODEL : PSP-600-24 1. ROOM AMBIENT BURN-IN : 1 HRS I/P: 230VAC O/P: FULL LOAD Ta= 33.6 °C 2. HIGH AMBIENT BURN-IN : 2 HRS I/P: 230VAC O/P: FULL LOAD Ta= 52.6 °C			P
2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR (MIN)	I/P: 230 VAC O/P: 111 % LOAD Ta:25°C	TEST : OK	P
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P: 230 VAC O/P: 100 % LOAD Ta= -20 °C	TEST : OK	P
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 45 °C NO DAMAGE	I/P: 272 VAC O/P: FULL LOAD Ta= 45 °C HUMIDITY= 95 %R.H	TEST : OK	P
5	TEMPERATURE COEFFICIENT	± 0.03 %(0-50°C)	I/P: 230 VAC O/P: FULL LOAD	± 0.01 %(0-50°C)	P
6	VIBRATION TEST	1 Carton & 1 Set Operating at I/P: 230VAC NO LOAD (1) Waveform: Sine Wave (2) Frequency:10-500Hz (3) Sweep Time:10min/sweep cycle (4) Acceleration:2G (5) Test Time:1 hour in each axis (X.Y.Z) (6) Ta:25°C		TEST : OK	P

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P: 3 KVAC/min I/P-FG: 1.5 KVAC/min O/P-FG: 0.5 KVAC/min	I/P-O/P: 3.6 KVAC/min I/P-FG: 1.8 KVAC/min O/P-FG: 0.6 KVAC/min Ta:25°C	I/P-O/P: 6.18 mA I/P-FG: 6.41 mA O/P-FG: 3.74 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P:500VDC>100MΩ I/P-FG: 500VDC>100MΩ O/P-FG:500VDC>100MΩ	I/P-O/P: 500 VDC I/P-FG: 500 VDC O/P-FG: 500 VDC Ta:25°C	I/P-O/P: 18G Ω I/P-FG: 11G Ω O/P-FG: 16G Ω NO DAMAGE	P
3	GROUNDING CONTINUITY	FG(PE) TO CHASSIS OR TRACE < 100 mΩ	40 A / 2min Ta:25°C	8 mΩ	P
4	APPROVAL	TUV: Certificate NO : R50051249 UL: File NO : E183223			P

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	PASS	P
2	CONDUCTION	EN55022 CLASS B	I/P: 230 VAC (50HZ) O/P:FULL/50% LOAD Ta:25°C	PASS Test by certified Lab	P
3	RADIATION	EN55022 CLASS B	I/P: 230 VAC (50HZ) O/P:FULL LOAD Ta:25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 LIGHT INDUSTRY AIR:8KV / Contact:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 LIGHT INDUSTRY INPUT: 1KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 LIGHT INDUSTRY L-N :1KV L,N-PE:2KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				



M.T.B.F & LIFE CYCLE CALCULATION

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	CAPACITOR LIFE CYCLE	SUPPOSE C205 IS THE MOST CRITICAL COMPONENT I/P: 230VAC O/P:FULL LOAD Ta= 25 °C LIFE TIME= 2220955 HRS I/P: 230VAC O/P:FULL LOAD Ta= 45 °C LIFE TIME= 655699 HRS			P
2	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT TOTAL FAILURE RATE: 116.4K HRS			P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	Q 52 Rated 2SK2850 : 900 V 6 A	I/P:High-Line +3V = 267 V O/P: (1)Full Load Turn on (2) Full Load (3)Output Short Ta:25°C	(1) 772 V (2) 804 V (3) 796 V	P
2	Diode Peak Voltage	D 72 Rated C25PQ60 : 60V 25A	I/P:High-Line +3V = 267 V O/P: (1)Full Load Turn on (2) Full Load (3)Output Short Ta:25°C	(1) 43.2 V (2) 52.2 V (3) 52.4 V	P
3	Clamp Diode Peak Voltage	D 50 Rated UF5408 3A/1KV	I/P:High-Line +3V = 267 V O/P: (1)Full Load (2) Dynamic Load 90%Duty/1KHz Ta:25°C	(1) 764 V (2) 764 V	P
4	Input Capacitor Voltage	C5 Rated :150 u / 400V/ 85°C	I/P:High-Line +3V = 267 V O/P: (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta:25°C	(1) 382 V (2) 382 V (3) 382 V	P
5	Control IC Voltage Test	U50 Rated 3845 : 30V	I/P:High-Line +3V = 267 V O/P: (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta:25°C	(1) 15.3 V (2) 13.3 V (3) 15.2 V	P

DATE	SAMPLE	TEST RESULT	TESTER	APPROVAL
2004/8/13	RD SAMPLE	PASS	VINCENT TSENG	MAX LIN
2004/11/9	PRODUCT SAMPLE W0409A42	PASS	VINCENT TSENG	MAX LIN
2005/1/5	PRODUCT SAMPLE W0411C25	PASS	VINCENT TSENG	MAX LIN

2003/12/12 A50-F023